



June 22, 2023

City of Tualatin

18880 SW Martinazzi Ave.
Tualatin, Oregon 97062

Site Location

TCS Fiber Installation

10699 SW Herman Rd.
Tualatin, Oregon 97062

Scope of Work

1. Install single mode 6-strand fiber between MDF and IDF as identified on the site drawing provided by the City of Tualatin.
2. Terminate two of the six strands. LC connectors will be used at the MDF and ST connectors will be used at the IDF.
3. Power meter test terminated fiber.

Quantity	Description	Cost
400'	Corning Single Mode 6-Strand Fiber	\$204.00
400'	Innerduct	680.00
2	FIS Wall Mount Patch Panel	208.00
1	FIS LC Adapter Plate	26.00
1	FIS 6 Port ST/UPC Adapter Plate	26.00
1	6 Fiber LC/UPC SM Pigtail Assembly	26.00
1	6 Fiber ST/UPC SM Pigtail Assembly	25.00
2	FIS Splice Tray	65.00
4	Fusion Splice	260.00
2	Power Meter Test	39.00
1	Labor – Fiber Termination	520.00
1	Mobilization	150.00
1	Labor – Fiber Installation	1,000.00
Total		\$3,229.00

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008 CCB 195629;
Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**