



June 14, 2023

EOCF
6907 E. 18th Street
Vancouver, Washington 98661

Cable Installation:

Scope of Work:

1. Provide and Install Cat. 6 CMR cable from patch panel to 8 data location (16 cables), 6 ceiling locations (6 cables), and 4 exterior locations (4 cables) identified on the site drawing.
2. Provide one (1) 10' patch cable and one (1) 2' patch cable for each cable run (excluding ceiling and exterior location).
3. Provide and install two (2) 24-port patch panel and one cabinet.
4. Test cables for Cat. 6 performance, label and document installation

Rate Schedule

Qty	Description	Cost
3,900'	Cat. 6 CMR Cable	\$1,365.00
250'	Wiremold	558.00
8	2 Port Faceplate	29.00
42	Cat. 6 Inserts	420.00
26	RJ-45 Mod Inserts	52.00
16	10' Patch Cables	133.00
26	2' Patch Cables	115.00
2	24-Port Patch Panel	110.00
1	Tripp Lite 4U Wall Mount Low Profile Rack Enclosure Cabinet	517.00
1	Misc. Materials	520.00
26	Cat. 6 Certification	390.00
1	Permit	175.00
	Labor	6,600.00
	Sub Total	\$10,984.00
	Tax --	955.61
	Total	\$11,939.61

Acknowledgement:

EOCF

Empower Digital Solutions, Inc.

 Authorized Signature Date

 Authorized Signature Date