



November 23, 2021

Portland Public Schools

Astor School

5601 N Yale St.

Portland, Oregon 97203

Scope of Work:

1. Remove projector and existing wood mount from auditorium.
2. Provide and install one projector pole mount from ceiling in auditorium in front of stage. Projector to be positioned in its current location.
3. Provide and install one (01) CAT 6 cable from MDF to projector location in auditorium.
4. Terminate the cable in an existing, discrete patch panel in the MDF.
5. Test the cable for CAT 6 performance, label and document installation.
6. Provide one (01) 100' HDMI cable.
7. Extend circuit to ceiling over projector.

Quantity	Description	Total Cost
200'	Cat. 6 CMR Cable – Blue	\$62.00
2	Cat. 6 Inserts	16.45
100'	HDMI Cable	262.00
1	Ceiling Mount / Extension Column	250.00
1	Faceplate – 1 Port	2.84
1	3' Cat. 6 Patch Cords – Black	3.78
10'	Wiremold	14.93
1	Cat. 6 Certifications	15.00
1	Limited Energy Permit -Minor Label	20.00
1	Miscellaneous Materials	50.00
1	Mobilization	135.00
	Labor	760.00
	Circuit Extension	1,235.00
	Lift – One Day Rental Including Delivery / Pick Up	515.00
TOTAL		\$3,342.00

Notes/Exclusions:

1. Empower Digital Solutions, Inc. meets and/or exceeds DCU Rates effective July 1, 2021.

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008 CCB 195629;
Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**