



February 8, 2022

Portland Public Schools
Gray Middle School
5505 SW 23rd Ave.
Portland, Oregon 97239

Scope of Work:

- 1. Provide and install two (02) CAT 6 cables from the MDF to the monitor location at the front entry of the school.**
- 2. Terminate the cable in an existing, discrete patch panel in the MDF.**
- 3. Test the cable for CAT 6 performance, label and document installation.**
- 4. Provide and install one (01) 3' CAT 6 patch cord at the patch panel and one (01) 10' CAT 6 patch cord for each cable.**
- 5. Install a 65" monitor provided by Portland Public Schools.**
- 6. Extend electrical circuit to new monitor location and install an outlet behind the new monitor location**

Quantity	Description	Total Cost
400'	Cat. 6 CMR Cable – Blue	\$124.00
4	Cat. 6 Inserts	32.00
1	Faceplate – 2 Port	3.00
2	10' Cat. 6 Patch Cords	14.00
2	3' Cat. 6 Patch Cords – Black	8.00
2	Cat. 6 Certifications	30.00
1	Limited Energy Permit – Minor Label	20.00
1	Miscellaneous Materials	80.00
1	Peerless TruVue Universal Tilting Wall Mount	40.00
1	Mobilization	135.00
	Labor	1,520.00
	Extend Circuit and Install Outlet for Monitor Above Tiles	1,140.00
TOTAL		\$3,146.00

Notes/Exclusions:

- 1. Empower Digital Solutions, Inc. meets and/or exceeds DCU Rates effective July 1, 2021.**

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008 CCB 195629;
Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**