



March 11, 2022

Portland Public Schools

Kenton School

4300 NE Killingsworth St.

Portland, Oregon 97218

Scope of Work:

1. Move monitor and mount in Room 109 to opposite wall, location identified in “site picture” provided by Portland Public Schools.
2. Provide and install two (02) CAT 6 cables from the MDF across the hall to a location behind the new monitor location.
3. Terminate the cable in an existing, discrete patch panel in the MDF.
4. Test the cable for CAT 6 performance, label and document installation.
5. Provide and install one (01) 3’ CAT 6 patch cord at the patch panel and one (01) 10’ CAT 6 patch cord for each cable.
6. Patch the wall behind the secretary and paint the repaired portion with Rodda Soft Shoulders (Paint Number 7972).
7. Extend electrical circuit to new monitor location and install a quad outlet behind the new monitor location.

Quantity	Description	Total Cost
400’	Cat. 6 CMP Cable – Blue	\$124.00
4	Cat. 6 Inserts	32.00
1	Faceplate – 2 Port	3.00
1	Rodda Soft Shoulders Paint – 1 Quart	24.00
2	10’ Cat. 6 Patch Cords	14.00
2	3’ Cat. 6 Patch Cords – Black	8.00
2	Cat. 6 Certifications	30.00
1	Limited Energy Permit – Minor Label	20.00
1	Miscellaneous Materials	100.00
1	Mobilization	200.00
	Labor	1,520.00
	Quad Outlet Installation	1,410.00
TOTAL		\$3,485.00

Notes/Exclusions:

1. Empower Digital Solutions, Inc. meets and/or exceeds DCU Rates effective July 1, 2021.

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008 CCB 195629;
Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**