



April 26, 2022

Portland Public Schools

BESC – Jonathan Garcia Office Monitor Installation

501 N. Dixon Street
Portland, Oregon 97227

Scope of Work:

1. Remove whiteboard on wall.
2. Provide and install four (04) CAT 6 cables from the IDF to a location behind the new monitor locations (previous whiteboard location).
3. Terminate the cable in an existing, discrete patch panel in the IDF.
4. Test the cable for CAT 6 performance, label and document installation.
5. Provide and install one (01) 3' CAT 6 patch cord at the patch panel and one (01) 3' CAT 6 patch cord for each cable.
6. Install two (02) monitors provided by Portland Public Schools.
7. Extend electrical circuit to new monitor location and install a quad outlet behind the new monitor location.
8. Demo cable in Reception area.
9. Drop data on wall in Reception Area.
10. Install blank at wall location at approximately 5'.

Quantity	Description	Total Cost
400'	Cat. 6 CMP Cable – Blue	\$124.00
8	Cat. 6 Inserts	64.00
1	Faceplate – 4 Port	3.00
1	Faceplate – 2 Port	3.00
2	Monitor Mounts	140.00
8	3' Cat. 6 Patch Cords – Black	32.00
4	Cat. 6 Certifications	60.00
1	Limited Energy Permit – Minor Label	20.00
1	Miscellaneous Materials	100.00
1	Mobilization	135.00
	Labor	1,900.00
	Quad Outlet Installation	1,330.00
TOTAL		\$3,911.00

Notes/Exclusions:

1. Empower Digital Solutions, Inc. meets and/or exceeds DCU Rates effective July 1, 2021.
2. Empower Digital Solutions, Inc. to provide two mounts for the two monitors

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008 CCB 195629;
Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**