



March 29, 2022

**Rick's Custom Fencing
8799 Portland Road NE
Salem, Oregon 97305**

Facility Cable Replacement Project

Scope of Work:

1. Provide and install one 2-post rack in MDF.
2. Move existing equipment to the new 2-post rack.
3. Remove approximately 40 existing cables.
4. Provide and install forty-two (42) CAT 6 cables from the MDF to locations including upstairs office outside server room (6 cables), downstairs office area (26 cables), warehouse time clock (2 cables), warehouse office (6 cables, machine at back of warehouse (2 cables).
5. Terminate the new cables in new patch panels in the MDF.
6. Provide and install one rack mount WBox UPS.
7. Test the new cables for CAT 6 performance, label and document installation.

Rate Schedule

Qty	Description	Cost
6,300'	Cat. 6 CMR Cable	\$1,953.00
1	Chatsworth 2-Post Rack	384.00
2	24-Port Patch Panel	104.00
1	WBox UPS – 1500 VA / 1050 W	496.00
84	Inserts	714.00
42	Cable Certifications	630.00
1	Misc. Materials	500.00
1	Limited Energy Permit	175.00
1	Mobilization	135.00
	Labor	6,400.00
	Total	\$11,491.00

Notes/Exclusions:

1. Proposal assumes carpeting is removed from location the new rack will be installed.
2. Prior to removing existing cable, Empower will evaluate cable for length, type, and if necessary, CAT 6 performance.

**Empower Digital Solutions, Inc. 7700 SW Hyland Way, Beaverton, Oregon 97008
CCB 195629; Electrical CLE290; ESB-8091 Erik J. Hopkins (503) 806-0530**